







# Massachusetts Water Resources Authority





# Deer Island Operations




■ Total Plant Flow, MGD   ■ 12 Yr Avg Flow, MGD   ● Total Precipitation, inches rain   ◇ 12 Yr Avg Precipitation, inches rain




# Deer Island Yearly Maintenance Metrics

Replacement Asset Value / Maintenance Technician






# Water Distribution System Pipelines





# Water Distribution System Valves

**Main Line Valves Exercised**




Type of Valve	Inventory #	Operable Percentage	
		FY14 to Date	FY14 Targets
Main Line Valves	2,092	97.7%	95%
Blow-Off Valves	1,206	95.1%	95%
Air Release Valves	1,335	93.1%	95%
Control Valves	48	100.0%	95%




# Wastewater Pipeline and Structure Inspections and Maintenance

## Inverted Siphon Cleaning





## Pipeline Cleaning





# Renewable Energy at MWRA









# Workforce Management

**Filled Position Tracking**



**Positions Filled by Hires/Promotions  
FY14-YTD**



	Pr/Trns	Hires	Total
FY11	48 (62%)	30 (38%)	78
FY12	42 (61%)	27 (39%)	69
FY13	82 (64%)	47 (36%)	129
FY14	111 (69%)	51 (31%)	162





# Massachusetts Water Resources Authority

*Presentation to the*


**Board of Directors**

***Existing and Future  
Combined Heat and Power (CHP)  
at DITP***

**September 17, 2014**



## DITP – A Significant Energy User




### **Staff efforts have helped reduced plant electrical demand by 10%**

- Process Optimization
- Installation of new energy efficient equipment



## DITP – Green Energy Production (FY14)

Total On-Site Renewable Electrical Energy Production, kWh



### Generation Assets:

- Digas – STG/BPSTG – 25.1 M kWh – 17.4%
- Hydro Power – 5.89 M kWh – 4.1%
- Wind Power – 1.48 M kWh – 1.0%
- Solar – 0.86 M kWh – 0.6%

### Maximizing On-Site Green Energy Production is a priority for MWRA

- 23% of DITP's total electricity demand met by green energy
- 60% of DITP's energy needs (heat + power) met by Digester Gas (62.5% for all)




## DITP – Digester Gas Generation & Use (FY14)




- Anaerobic Digestion:
  - 240 dtpd solid in, 100 dtpd to FRSA for pellet conversion
  - Digas generated on average is 60% methane
- OSTPP: Bottom-Cycle Generation
  - Digas – 95% utilized
  - 95% of heat demand met by Digas (\$17.6 million annually) (remainder by Fuel Oil)
  - 25.1 M kWh generation from Steam Turbine (\$2.4 million annually)



# Combined Heat & Power Process – Currently Used by DITP



- **Bottom Cycle Generation**
  - Heat First – 60% efficient
    - Generate Steam then Hot Water
  - Power Second – 9% efficient
    - Generate Electricity from Steam
- New BPSTG / Steam Bypass Valve improves steam to electricity conversion process by extracting more heat per unit steam






# Combined Heat & Power Process – Improved Performance

## STG Power Output vs. Steam Flow

(STG Boiler 101 with BP-STG)



- **New BPSTG / Steam Bypass Valve improve steam to electricity conversion process**
  - 18% improvement (10.6% efficiency overall)
  - +1.3 MW increase in generation from steam generators
  - Sustainable May - November
  - Should see an increase of +4.5 M kWh / year
  - ~30 M kWh total/year from steam (25.1 M kWh currently)







## CHP Study Objectives – CDM Smith Residuals Technology Assessment

- Develop engineering and economics for new CHP
- Compare and recommend more efficient generation technologies
  - Internal Combustion Engines
  - Gas Turbines
- Develop Simple Payback Analysis / Economic benefits
- Evaluate implementation options



## Internal Combustion Engines versus Gas Turbines

- Exhaust emissions (NO<sub>x</sub>, CO) – GT ↓
- Space required (Capacity) – GT ↓
- Capital and operating costs – GT ↓
- Energy efficiency (Electricity and Heat) ↔
- Flexibility – GT ↑







# CHP Technology Change

## CHP Technology Change

- Change from Bottom to Top cycle generation
- Improve efficiency
- Increased electrical production
- Better use of all digas - summer months
- Continue to meet plant heating needs

## CHP Benefit from Co Digestion

- Expected 29-42% increase in biogas
- Results in more electrical output
- Heat demand increase 5-10%
- Electrical demand increase <2%





## Cost Benefit Analysis – Simple Payback

### Payback Without and With Co-Digestion


Parameter	OSTPP with 1 Gas Turbine*	OSTPP with 1 Gas Turbine* With Co-digestion	3 Gas Turbines*	3 Gas Turbines* With Co-digestion
Capital Cost	\$24.9 M	\$24.9 M	\$75.0 M	\$75.0 M
Annual O&M Cost	\$2.2 M/yr	\$2.2 M/yr	\$1.6 M/yr	\$1.6 M/yr
Annual Electrical Savings	\$5.2 M/yr	\$7.0 M/yr	\$11.4 M/yr	\$14.7 M/yr
Net Annual Savings	\$3.0 M/yr	\$4.8 M/yr	\$9.8 M/yr	\$13.1 M/yr
Simple Payback Period	8 years	5 years	8 years	6 years

- Single Gas Turbine capacity: 4.6 MW
- Payback does not include potential funding for green energy projects to pay for the capital.




## Potential Energy Benefit with CHP

### Existing Thermal Plant



- 23% green generation\* (18% w/digas)
- 75% purchased electricity

### CHP with 3 Gas Turbines – Co-Digestion





- Can reverse energy profile
- More sustainable
- 77% green generation\* (72% w/digas)
- 21% purchased electricity

\*Note: 1.5% generation by CTG backup power.



## Recommendation

- Gas Turbine CHP is recommended technology
- Staff will move forward with design to
  - Confirm economics
  - Investigate additional equipment needed
  - Review economics with and without co-digestion
  - Confirm full implementation approach
  - Develop specific gas system changes
  - Develop plans and specs for bidding new CHP







# Massachusetts Water Resources Authority

*Presentation to the*

**Board of Directors**

## *Struvite , Scum, Sludge, and Grit Removal Contract*

September 17, 2014





# Struvite Removal

## Cause

- Struvite forms a pipe scale and consists of phosphate, ammonia, and magnesium
- Struvite coats digested sludge pipelines
  - Digester overflow box piping
  - Centrifuge piping
- Difficult to remove

## Prevention

- Ferric chloride added to control

## Remediation

- Specialized equipment and services in confined spaces needed for removal





## Scum, Sludge and Grit Removal

- Removal of severe blockages beyond in house capability in:
  - Gravity thickeners
  - Primary clarifiers
  - Influent channels
  - Scum receiving wells
- Vactor trucks and boxes used
- Off site material disposal







# Massachusetts Water Resources Authority

*Presentation to the*

**Board of Directors**

## *Deer Island Clarifier Rehabilitation Contract 7394*

September 17, 2014



## Deer Island Stacked Clarifiers





## Condition of Concrete







# Massachusetts Water Resources Authority

*Presentation to the*

**Board of Directors**

***Beacon Street Line:  
Water Pipeline Repair  
Contract 7474***

September 17, 2014






## Beacon Street Line - Brookline

- 48-inch cement mortar lined cast-iron pipe
- Constructed in the 1870s it is part of MWRA's Boston Low Service System
- A significant portion of it is located underneath the MBTA's Beacon Street Green Line tracks
- The Beacon Street Line provides important the Longwood Medical area





# Beacon Street Line - Brookline







## Location of Access Pits

**ACCESS PIT # 1**



**ACCESS PIT # 2**



CFRP Installation



# Massachusetts Water Resources Authority

*Presentation to the*


**Board of Directors**

***Spot Pond Water Storage Facility  
Contract 6457, Change Order 7***

September 17, 2014



# Spot Pond Tank and Ravine Road Piping





## Remove Ledge to Install 36-Inch Pipelines and Valve Vaults at Ravine Road





## Remove 87 Linear Feet of 16-Inch-Diameter, Cast-Iron Water Main and Replace with Restrained-Joint, Ductile-Iron Pipe







# Current Progress





# Massachusetts Water Resources Authority

*Presentation to the*

**Board of Directors**

## *Gillis Pump Station Short-Term Improvements Contract 7260, Change Order 3*

September 17, 2014



## Additional Valve Work





## Ledge Croppings Inside Excavated Pit





## Selector Switch for Three VFD Bypasses



