
Alewife Brook Pump Station Rehabilitation Design/CA/RE Services Contract 7034 – Amendment No. 3

April 12, 2017



Alewife Brook Pump Station





Work to date:

- Installation of flood control measures at exterior openings
- Construction of bypass pumping system discharge vault
 - Will later serve as the Alewife Brook Conduit meter vault
- Installation of bypass pumping system pumps, piping and valves
- Commencement of PCB remediation

Upcoming work:

• Full bypass, then station rehabilitation

Substantial Completion May 2018









Construction of Bypass System Discharge Vault



Installation of Bypass System Pumps and Suction Lines



1 17 10



Additional Contractor Submittal Review Services \$95,266

- Contract quantity of 220 has been reached
- Additional 167 submittals projected to be reviewed
- Cost based on actual incurred for the initial 220 submittals




Reading Extension Sewer and Metropolitan Sewer Rehabilitation Contract 7164

April 12, 2017

Original Construction circa 1919

Construction of a Section of the Reading Extension Sewer (circa. 1919) along Prospect Street near the Stoneham/Wakefield town line.

7164 Project Limits (Stoneham, Woburn and Wakefield)




6



7164 Project Information and Summary

- Reading Extension Sewer 12,240 feet of 15, 18, 20-in VC constructed in 1919
- Metropolitan Sewer 2,280 ft of 15-in VC constructed in 1890s
- Both sewers revealed both structural and nonstructural deficiencies during CCTV inspections





7164 Project Information and Summary

- Rehabilitation of 13,100 ft of pipe utilizing Cured-in-Place Pipe (CIPP) and lining 62 manholes and structures
- Bypass pumping and flow diversions
- Coordination with other projects (MWRA NIH, Eversource Energy and Rail Trail)





• Bids opened on February 23, 2017

ContractorBid AGreen Mountain Pipeline Services, Inc.\$2,0Insituform Technologies, LLC\$2,1Layne Inliner, LLC\$2,8Engineer's Estimate\$4,2

Bid Amount

\$2,048,945 \$2,154,000 \$2,891,160 *\$4,240,000*

• Staff recommend to award Contract 7164 to Green Mountain Pipeline Services, Inc.



- More Aggressive Installation Rate (fewer lining setups):
 - Insertion lengths longer than assumed
 - Lower equipment time/labor hours
 - Reduction in bypass pumping time
 - Less traffic maintenance (Police and devices)
- Lower overhead with lining company General Contractor
- More aggressive bid as a past General Contractor and subcontractor for MWRA
- Close range of bids indicates correct level of effort to successfully complete project



Contract Award to:	Green Mountain Pipeline Services, Inc.
Contract Bid:	\$2,048,945
Notice to Proceed:	May 2017
Contract Substantial Completion:	August 2018
Contract Duration:	487 calendar days




Section 80 Repair MWRA Contract No. 7532

Construction Update April 12, 2017



Section 80 Repair Locus Plan







Section 80 Emergency Repair MWRA Contract No. OP-352 Construction Update April 2-3, 2017





Date: 4/11/2017 1 incn = 370 feet 4/11/2017 5ecurity Operational - For MVRA use ONLY 0 320 6e0 1,280 Feet 5





Cutting pavement in lane 4/2, 10:15 P.M.

Buried manhole cover found 4/2, 10:45 P.M.





Air Release Valve assembly installed on existing pipe 4/2, 11:55 P.M.

Air Release Valve Assembly (mounted on flanged plate)



Sect

Section 80 Emergency Repair



Top of Flange without A.R.V 4/3, 12:05 A.M.

New Flange Plate installed 4/3, 12:40 A.M.





Prepared Trench 4/3, 1:20 A.M.

Backfilled with CDF 4/3, 1:30 A.M.







Temporary Trench paving 4/3, 2:40 A.M.





• Leak at 6:00 on pipe between removed thrust block and coupling







Excavation and Repair





Form for Thrust Block






Quabbin Reservoir and Drought Status Update

April 12, 2017

Massachusetts Drought Status March 1, 2017



National Drought Mitigation Center Intensity Map April 4, 2017


U.S. Drought Monitor Massachusetts

April 4, 2017 (Released Thursday, Apr. 6, 2017) Valid 8 a.m. EDT

Drought Conditions (Percent Area)

	None	D0-D4	D1-D4	D2-D4	D3-D4	D4
Current	33.19	66.81	16.65	0.00	0.00	0.00
Last Week 03-28-2017	1.34	98.66	66.79	14.73	0.00	0.00
3 Month s Ago 01-03-2017	0.70	99.30	98.09	69.13	8.59	0.00
Start of Calendar Year 01-03-2017	0.70	99.30	98.09	69.13	8.59	0.00
Start of Water Year 09-27-2016	0.00	100.00	98.15	89.95	52.13	0.00
One Year Ago 04-05-2016	80.30	19.70	0.00	0.00	0.00	0.00

Intensity:



D3 Extreme Drought

ught D4 Exceptional Drought

D2 Severe Drought


The Drought Monitor focuses on broad-scale conditions. Local conditions may vary. See accompanying text summary for forecast statements.

<u>Author:</u>


Anthony Artusa NOAA/NWS/NCEP/CPC



http://droughtmonitor.unl.edu/



Quabbin Volume 1/1/2000 to 4/11/2017






- Staff contacted community elected officials and water superintendents with pointers to water conservation
- MWRA sent out Public Service Announcements asking residents and businesses to conserve water
- MWRA used its website and social media to draw awareness of the need to conserve
- The target is to keep water usage at previous year levels without issuing mandatory restrictions




Overall Demand Tracking Lower Than Last Year

Fully Supplied Communities



Partially Supplied Communities





Status Looking Forward from April 1, 2017


	1-Month	3-Months	6-Months	12-Months
Median Yield	Below Normal	Normal	Normal	Normal
Dry (75th Percentile)	Below Normal	Below Normal	Normal	Below Normal
Driest (of Record)	Below Normal	Below Normal	Below Normal	Drought Warning




Stage	Target Water Use Reduction
Normal Operation	0
Below Normal	Previous year's use (Voluntary)
Drought Warning	5% (Primarily Voluntary)
Drought Emergency	(Mandatory Restrictions)
Stage 1	10%
Stage 2	15%
Stage 3	30%



Quabbin's Long-term Track



Rainfall Deficit Reducing In The Service Area





Wachusett Elevation 2017

