



Massachusetts Water Resources Authority

Update on Containment Spill Response Program at Reservoirs

December 19, 2018



Threats In The Watersheds

Roadway Threats:

- Over 100 miles of roadway combined in watersheds
- Fuel oil /heating oil trucks
- Saddle tanks on large trucks

Railroad (Wachusett only):

- Staff reviews RR cargo manifests
- Response operations depend on the type of spill





Equipment: 8 Response Trailers Staged at Quabbin and Wachusett















Equipment: Several MWRA, DCR and FD Boats Available








DCR-DWSP





Equipment: Remote Rt. 202 Quabbin West Branch Boom Shed














Equipment: Cosgrove Intake Boom Staged For Rapid Boat Response
















Prepositioned Boom Anchor Points For Strategic Collection








Training: Experienced, Engaging Trainer Key For Skills Reinforcement





Training: Night Operations Take More Detailed Planning Due To Safety Concerns















Training: Local Watershed Fire Departments Important Partner











Booming Techniques: Vary To The Spill And Conditions











Booming: Open Water Floatable Contaminant Collection





Booming: MWRA ESU Metro Training At Spot Pond













Booming: Watershed Tributary Spill Response





Response: Actual release incidents that put training into action


2008 - Rt 140 diesel release at Wachusett Reservoir

- 2010 Discarded 55-gal. drum discovered at Quabbin watershed
- 2016 Car in water at Spot Pond

2018 – Vehicle accident at Ware River Shaft 8 Intake



Response To Diesel Spill On January 2, 2008





Response: Watershed Staff Played A Crucial First Responder Role On January 2. 2008 Diesel Spill











Response: Discarded Drum In Quabbin Watershed In 2010





Response: Vehicle Accidents At MWRA Facilities



Spot Pond 2016




Ware River Shaft 8 Intake 2018



Removal of Direct Discharges from Roadways at Wachusett



Phase II areas: Completed 2017



Phase I, Cosgrove Intake area: Completed





Direct Discharge Basins, Dry And Post-storm Detention












Remaining Challenges - Railroad Crossing Watershed










Massachusetts Water Resources Authority

Northern Intermediate High Service Redundant Pipeline Contract 6906, Amendment 3

December 19, 2018



NIH Contract 6906 Stantec Consulting Services



- Occupant (\$2,230,715)
 - 2,400 linear feet of 36-inch pipeline
 - Completed May 2015.
- Contract 7471: (12,230,715)
 - 8,800 linear feet of 36-inch pipeline
 - Completed December 2017
- Contract 7478: (\$18,512,415)
 - 7,800 linear feet of 48-inch pipeline
 - 2,600 linear feet of 16 and 12-inch pipeline
 - Completed September 2018
- Contract 7067: (\$22,737,300)
 - 14,000 linear feet of 48-inch pipeline
 - NTP June 2017/Completion June 2020
 - 7,500 linear feet installed to date

Total Construction Cost \$55,700,000



NIH Contract 6906 Stantec Consulting Services

Amendment 3 Summary

Out of Scope Changes	\$285,500 *
Additional Local Record Drawings	\$137,500
Re-Stationing of Section 110	\$45,000
TOTAL	\$468,000

^{*} Offset by settlement agreement of \$80,000 for design error on Oak Street drain line rework



NIH Stoneham Meter 122 Installation






NIH Reading Meter Cabinet and Line Valve Bypass





NIH Additional Drawing Updates



Re-Stationing of MWRA Section 110 Drawings

- 13,100 linear feet of 36-inch pipeline
- 21,800 linear feet of 48-inch pipeline
- 2,600 linear feet of 12/16 -inch pipeline
- Five separate construction contracts
- Three separate design consultants

Local Water, Drain, and Sewer Drawings

18,750 linear feet of 4 to 30 inch diameter





Massachusetts Water Resources Authority

Delegated Authority Report

December 19, 2018



Recent Vehicle Purchases - Pricing

MSRP vs. Bid Price

Vehicle	MSRP	Liberty Chevrolet	Colonial Ford
2019 GM K3500 Double Cab	\$77,915.00	\$65,464.00	\$64,389.50
Equinox SUV	\$33,001.25	\$29,164.00	\$31,284.00
GM Bolt	\$47,720.62	\$40,656.00	\$41,848.75
GM 2500 155" WB Series Van	\$49,281.25	\$40,560.00	\$39,768.50

Prices include Fees, Options, and Outfitting

Competition Across Bid Items

Vehicle	Quantity	Liberty Chevrolet	Colonial Ford
K3500 Double Cab	1	\$65,464.00	\$64,389.50
K1500 Double Cab	1	\$35,121.50	\$32,086.10
K2500 Double Cab, no plow	1	\$37,660.00	\$36,735.35
K1500 Double Cab (slightly different lighting package than line #2)	2	\$69,813.00	\$63,947.20
Colorado Crew Cab	2	\$78,726.00	\$82,575.50
K2500 Crew Cab	3	\$193,972.80	\$205,231.50










Massachusetts Water Resources Authority

Change Order Requests on Active Construction Projects

December 19, 2018









Massachusetts Water Resources Authority

(Not presented)

FY2020 Proposed Capital Improvement Program

December 19, 2018



Massachusetts Water Resources Authority

FY20 Proposed Capital Improvement Program

December 19, 2018


FY20 Proposed CIP complies with the Cap requirements

Focus on Asset Protection and Long-Term Redundancy

Metropolitan Tunnel Redundancy



FY20 Proposed CIP





FY20 Proposed CIP - FY19-23 Base-Line Cap

		FY19	FY20	FY21	FY22	FY23	Total FY19-23
FY20 Proposed	Projected Expenditures	\$174.3	\$249.8	\$258.7	\$218.8	\$182.3	\$1,083.9
	I/I Program	(29.0)	(25.7)	(25.0)	(28.2)	(26.9)	(134.8)
	Water Loan Program	(22.4)	(9.7)	(5.2)	(4.4)	4.2	(37.5)
	MWRA Spending	122.9	214.4	228.5	186.1	159.6	\$911.6
	Contingency	0.0	13.6	14.8	12.5	10.7	51.6
	Inflation on Unawarded Construction	0.0	2.1	5.5	6.2	7.6	21.4
	Chicopee Valley Aqueduct Projects	(0.0)	0.0	0.0	0.0	0.0	(0.0)
	FY19 Proposed FY19-23 Spending	\$122.9	\$230.1	\$248.8	\$204.7	\$178.0	\$984.6

		FY19	FY20	FY21	FY22	FY23	Total FY19-23
FY19 Final	Projected Expenditures	\$179.2	\$276.1	\$251.3	\$194.9	\$150.4	\$1,051.8
	I/I Program	(19.2)	(25.7)	(24.3)	(27.9)	(26.1)	(123.2)
	Water Loan Program	(8.3)	(8.4)	(7.2)	(5.6)	(2.8)	(32.4)
	MWRA Spending	151.7	241.9	219.7	161.4	121.4	\$896.2
	Contingency	9.9	15.9	14.5	11.0	8.2	59.4
	Inflation on Unawarded Construction	0.7	5.0	7.8	7.2	8.5	29.3
	Chicopee Valley Aqueduct Projects	(0.0)	0.0	0.0	0.0	0.0	(0.0)
	FY19 Proposed FY19-23 Spending	\$162.3	\$262.8	\$242.0	\$179.6	\$138.1	\$984.8



FY20 Proposed CIP – Top Construction Projects (\$ in 000s)

Project Contract		FY20 Proposed Spending
DI Treatment Plant Asset Protection	Clarifier Rehab Phase 2 - Construction	\$23.1
Facility Asset Protection	Chelsea Creek Upgrades - Construction	\$19.3
Facility Asset Protection	Prison Point Rehabilitation Construction	\$18.6
Corrosion & Odor Control	Nut Island Odor Control HVAC Improvement Construction Ph 2	\$10.0
DI Treatment Plant Asset Protection	HVAC Equipment Replacement Construction	\$8.0
SEH Redundancy & Storage	Redundancy Pipeline Sect 111 - Construction 3	\$7.0
Residuals Asset Protection	Residuals Electrical/Mechanical/Drum Dryer Replacement	\$6.4
DI Treatment Plant Asset Protection	Gravity Thickener Rehabilitation	\$6.3
New Connecting Mains -Shaft 7 to WASM 3	CP3 Sections 23, 24, 47 Rehabilitation	\$6.0
Total		\$104.7
% of Total FY20 Proposed MWRA Spending		41.9%


FY20 Proposed CIP

Spending Composition				
Ongoing Awarded Contracts	\$67.3M			
Proposed Contract Awards	\$182.5M			
Total Proposed Expenditures	\$249.8M			



FY20 Proposed CIP – Proposed FY20 Expenditures

Total Proposed FY20 Expenditures: \$249.8 million





FY20 Proposed CIP – New Projects

Total New Projects Added in FY20: \$54.5 million

- Wastewater: \$48.8 million
- Waterworks: \$0.8 million
- Business & Operations Support: \$5.0 million



FY20 Proposed CIP – New Projects

- Pump Stations & CSO Facility Rehabilitation: \$45.0 million
- As-Needed Design Contracts 18 and 19: \$5.0 million
- Deer Island Resident Engineering Inspection: \$3.0 million
- Carroll Water Treatment Plant Emergency Generator No. 1
 Replacement (Electric Portion) \$0.8 million
- Sections 191 & 192 Charles River Valley Sewer \$0.5 million
- Clinton Wastewater Treatment Plant Equipment & Supplies Storage Building - \$0.3 million



FY20 Proposed CIP – Top New Project

• Pump Stations & CSO Facility Rehabilitation: \$45.0 million







FY20 Proposed CIP – Asset Protection and Water Redundancy

Project Category	FY14-18	FY19-23	FY24-28
Asset Protection	\$284.6	\$773.4	\$1,095.4
Water Redundancy	174.6	213.2	\$373.5
CSO	64.7	7.7	\$0.0
Other	61.7	89.6	\$109.5
Total	\$585.6	\$1,083.9	\$1,578.4
Asset Protection	48.6%	71.4%	69.4%
Water Redundancy	29.8%	19.7%	23.7%
CSO	11.0%	0.7%	0.0%
Other	10.5%	8.3%	6.9%
Total	100.0%	100.0%	100.0%

 Asset Protection and Redundancy are the principal drivers of future capital expenditures



Asset Protection

Preserve the condition of assets

- Asset Protection in CIP
- Day to Day Maintenance in CEB



FY20 Proposed CIP – FY20 Top Spenders – Asset Protection

Clarifier Rehabilitation Phase 2 Construction

FY 20 Budget: \$23.1M

Total Contract: \$135.0M

NTP: February 2019

SC: November 2022









FY20 Proposed CIP – FY20 Top Spenders – Asset Protection

Chelsea Creek Headworks Upgrade Construction

FY20 Budget: \$19.3M

Total Contract: \$81.8M

NTP: November 2016

SC: November 2020







FY20 Proposed CIP – FY20 Top Spenders – Asset Protection

Prison Point Rehabilitation Construction



FY 20 Budget: \$18.6M

Total Contract: \$36.3M

NTP: July 2019

SC: July 2021







FY20 CIP – FY20 Top Spenders - Asset Protection

Nut Island Odor Control & HVAC Improvements Construction

FY 20 Budget: \$10.0M

Total Contract: \$39.9M

NTP: May 2019

SC: September 2022









FY20 CIP – FY20 Top Spenders - Asset Protection

Deer Island HVAC Equipment Replacement Construction

FY 20 Budget: \$8.0M

Total Contract: \$40.2M

NTP: March 2019

SC: September 2022









FY20 CIP – FY20 Top Spenders - Redundancy

Southern Extra High Redundancy


Section 111 Construction 3

FY 20 Budget: \$7.0M

NTP: June 2018

SC: September 2020







FY20 CIP – FY20 Top Spenders - Asset Protection

Residuals Electrical/Mechanical/Drum Replacement

FY 20 Budget: \$6.4M

NTP: June 2019

SC: December 2020









FY20 CIP - FY20 Top Spenders - Asset Protection

Gravity Thickener Rehabilitation

FY 20 Budget: \$6.3M

NTP: May 2018

SC: February 2021







FY20 CIP - FY20 Top Spenders - Asset Protection

New Connecting Mains CP3 Sections 23, 24,27

Rehabilitation

FY 20 Budget: \$6.0M

NTP: April 2019

SC: March 2022








FY20 Proposed CIP – Proposed FY20 Contract Awards

- 54 FY20 Contract Awards
- Total Contract Value: \$182.5 million






FY20 Proposed CIP - Projected Contract Awards (\$s in millions)

Project	Subphase	Notice to Proceed	Total Contract Amount
Facility Asset Protection	Prison Point Rehabilitation - Construction	Jul-19	\$36.3
DI Treatment Plant Asset Protection	Fire Alarm System Replacement - Construction	Aug-19	\$22.0
Metropolitan Redundancy Interim Improvements	WASM 3 CP-1	Jan-20	\$20.4
NIH Redundancy & Storage	Sections 89 & 29 Replacement - Construction	May-20	\$16.0
Facility Asset Protection	Ward St & Columbus Park Headworks Design/CA	Feb-20	\$11.4
Metropolitan Tunnel Redundancy	Preliminary Design & MEPA Review	Apr-20	\$9.3
DI Treatment Plant Asset Protection	Digester & Storage Tank Rehabilitation Design/ESDC	Jan-20	\$4.1
DI Treatment Plant Asset Protection	DI Dystor Membrane Replacements	Jul-19	\$4.0
Wastewater Meter System-Equipment	WW Metering Asset Protect/Equip. Purchase	Aug-19	\$4.0
Watershed Division Capital Improvements	Maintenance Garage/Wash Bay/Storage Building Construction	Apr-20	\$3.9
Top 10 Contract Awards			6124.2
Top 10 Contract Awards			\$131.3
54 Contract Awards Planned for FY20			\$182.5




Historic and Projected Capital Improvement Spending







Historic and Projected Capital Improvement Spending by Utility






Level of MWRA Indebtedness







Capital Spending and Debt Service





- Metropolitan Tunnel Redundancy
- Lessons learned from Chelsea Headworks Upgrades
- Continue Asset Protection




Metropolitan Tunnel Redundancy Program

FY19-23 Projected Expenditures

Contract Name	Start/ Duration (years)	Contract Budget (millions)	FY19-23 Spending (millions)
Program Support Services	FY19/9	\$13.6*	\$6.0
Preliminary Design/MEP A Review	FY20/3	\$9.3	\$9.0

^{*}FY20 dollars. Escalation not included.





Work with the Advisory Board

Finalize FY20 CIP

 Submit FY20 Final CIP to Board of Directors for approval in June 2019



THANK YOU







Massachusetts Water Resources Authority

Update on Construction of Cross-Harbor Cable

December 19, 2018




Eversource Cable Route





Construction Methods (Horizontal Directional Drilling)



Drill Bits



Construction (HDD-Conley Terminal)





- Approx. 3300' HDD on Conley Terminal side
- Approx. 1100' HDD on Deer Island side
- Four total passes (9-7/8", 24", 30" and 36")



Construction Methods (Hydroplow)





Construction Methods (Hydroplow)





Construction Methods (Open Excavation-Conley Terminal)







Construction Methods (Open Excavation-Deer Island)







Construction Methods (Open Excavation-Deer Island)








Marine Cable Information



3 115 kV Submarine Cable Supply

3.1 Cable Diagram



(For information only - not to scale)

Description	
1. Copper wires	7. Core Jacket
2. Conductor screen	8. Fillers
3. XLPE Insulation	9. PP string bedding
4. Insulation screen	10. Mixed (Galvanised Steel + PE) wire armour
5. Water Blocking tape	11. PP string serving
6. Metallic shield	12. Optical Unit

DISCLAMPER: The document contains information in propertient by the DISCHAMP INVESTIGATION OF the reproduced or transferred to other documents or disclassed to others or used for any purpose offer than that for which it is furnished without the certification of the other produced or transferred to other contained without the other produced or transferred or transferred to other or used for any purpose offer than that for which it is furnished without the certification of the other produced or transferred or transferred to other or used for any purpose offer than that for which it is furnished.

- New 115KV Submarine cable manufactured by Prysmian Group
- Solid Dielectric vs oil filled cable
- Same capacity 90MVA



Eversource HDPE Fusing Operation





Construction Progress





Construction Schedule

HDD drilling

January 2019

Hydroplowing

February 2019

Marine cable installation

April 2019

New cable testing period

August 2019

Cable placed into service

September 2019

• Existing cable removal

December 2019





Massachusetts Water Resources Authority

Refurbishment of Secondary Reactor Aerator and Mixer Gearboxes at Deer Island Bid WRA-4594

December 19, 2018



Deer Island Secondary Treatment


- Cryogenic Oxygen Generation
- **Secondary Reactors**
- **Secondary Clarifiers**





Deer Island Secondary Reactor Gearboxes

- A Critical Component of Oxygen Reactors
 - Provides for oxygen transfer
 - Promotes biomass growth for treatment
 - Mixer/Aerator system:
 - Drives, Motors, Gearboxes & Mixers
 - 9 Trains x 8 Gearboxes = 72 units
 - 6 Trains operate 24/7
- Equipment Age: 17-21 years
- Expected Service Life for Gearboxes: 11 years





Procurement: Refurbishment basis & Award Recommendation

Annual refurbishment plan, as required:

- 6 50 hp units (18 during contract term)
- 1 150 hp unit (3 during contract term)
- 6 100 hp units (18 during contract term)



- 2 Vendors submitted bids
- Lowest Bidder: SPX Corporation (incumbent and OEM)
- Not to exceed \$885,936
- 3-Year Term



Low Speed Gear