





**Massachusetts Water Resources Authority** 






### **Wet Fall Results in Increased Plant Flow**






### **Higher Flow Requires More Energy**






### **CTGs Run During Storms for Reliability**





### **Drinking Water Source Water**







### **Treated Water Quality**


#### MetroBoston Disinfection By-Products






#### CVA Disinfection By-Products (Combined Results)








### **Wastewater Structure Inspections and Maintenance**



Staff inspected 12 siphon barrels this quarter. Year to date total is 12 inspections.



Staff cleaned 20 siphon barrels during this quarter. Year to date total is 37.



## **Leak Detection and Repair**

	Leak Backlog Summary									
Month	J	А	S	О	N	D	Totals			
Leaks Detected	1	4	4	1	0	1	11			
Leaks Repaired	0	0	3	7	2	1	13			
Backlog	10	14	15	9	7	7	n/a			

During the 2nd Quarter of FY19, two new leaks were detected, ten leaks were repaired







### **Massachusetts Water Resources Authority**

# MWRA Fiscal Year 2020 Proposed Current Expense Budget

February 20, 2019

## Rates Management Strategy

Sustainable and Predictable Assessments

Multi-Year Approach




### **Budget Drivers For Multi-Year Planning**

- Capital Finance Expenses
- Existing Expenses and Revenue Inflation, Changes
- Long-Term Liabilities




### **Historical Budgeted Spending**





#### **Before and After Defeasance**





## **Expense Changes - HEEC**

	FY19	FY20	FY21	FY22	FY23	FY24
Projected HEEC Expense  Net of \$6.5 reserve	\$1.4	\$4.4	\$5.2	\$6.3	\$6.4	\$6.7

Amounts in millions



## **Long-Term Liabilities**


Pension Funding Schedule		\$7.3			
OPEB Funding Schedule	<b>FY19</b> \$5.6	<b>FY20</b> \$6.0	<b>FY21</b> \$6.1		

Amounts in millions



### **CEB Budget Structure**


- Direct Expenses
- Indirect Expenses
- Capital Finance Expenses
- Non-Rate Revenue
- Rate Revenue





## FY20 Proposed Current Expense Budget (CEB)

#### **FY20 Proposed Current Expense Budget**






### **CEB Budget Highlights – Direct Expenses**

### **Direct Expenses**


(\$s in millions)




- Wages, Salaries, Overtime
   & Fringe Benefits: Reflects
   collective bargaining and
   tunnel redundancy staff
- Chemicals: \$1.2 M million increase
- Utilities: \$1.3 million increase
- Maintenance: \$.5 million increase




### **Historical & Projected Chemical Cost**







#### **Diesel Fuel**



#### **Health Insurance FY11-FY20**






54%

### **CEB Budget Structure – Indirect Expenses**

### **Indirect Expenses**




- Pension Fund: 95% funded
- OPEB Contribution: 50% of **Actuarially Determined Contribution**
- HEEC Cable: New cable coming online in FY20
- Watershed & PILOT: \$0.79 million increase



### **CEB Budget Structure – Capital Finance Expenses**


#### **Capital Financing**

(\$s in millions)



- Variable Rate Debt Assumption: 3.75%, 25 basis point increase
- Assumes \$15.0 million defeasance in FY19
- \$1 million increase to Current Revenue for Capital
- \$4.9 million prepayment of debt

#### **MWRA All-In Cost of Variable Rate Debt**






#### **FY20 Non-Rate Revenue**

#### **Non-Rate Revenue**


(\$s in millions)



- Investment Income: Short-term assumption increasing 50 basis points from 1.75% to 2.25%
- Other revenue: Reduction due to demand response and RPS programs
- Other User Charges: Reduction related to Entrance Fees and Water Treatment Residuals




### **Actual and Forecasted Rate Revenue Changes**





### **Actual and Forecasted Rate Revenue Changes by Utility**





### **FY20 Current Expense Budget Next Steps**

- Transmit Proposed Budget to Advisory Board for 60 day review
- Public Hearing
- MWRA Board Hearing
- Staff will present Draft Final Budget in May
- Staff anticipate FY20 Budget adoption in June





## **Thank You**





### **Massachusetts Water Resources Authority**

## Amendments to MWRA TRAC Regulations

February 20, 2019



### 360 CMR 10.000: Sewer Use

Intended to protect the public health, safety, and welfare and the environment to ensure proper and safe operation of MWRA's wastewater treatment facilities by regulating the direct and indirect discharge of wastewater and pollutants to MWRA's Sewerage System

#### **Key Proposed Revisions:**

- Creates a Group Permit for Dental Discharges
- Incorporates requirements for onetime only Discharges
- Allows for electronic submittals
- Allows for permitted Reclaimed Water Systems to discharge municipal sludge to the sewer
- Updates Clinton local limits
- Updates Incentive Program Charges



### 360 CMR 10.065: Group Permit for Dental Discharges

- Incorporating Requirement from:
  - 40 CFR Part 441
  - MassDEP: Amalgam and Wastewater Recycling for Dental Facilities, 310 CMR 73.00
- Group Permit for Dental Discharges (Category D1)
  - Universe of new facilities: ~1,000
  - Place or remove amalgam, except in emergency situations
  - BMP based requirements
    - Requires a properly sized amalgam separator
    - Removal efficiency of 98%
    - Proper maintenance
    - Can only use specific disinfectants and cleaning agents (no bleach, non-corrosive)
    - Retain all paperwork



### 360 CMR 10.101 and 10.102: Incentive Program Charges

- Increases permit and monitoring charges by 4% in FY20
- Increases permit and monitoring charges by 3% in FY21 through FY24
- Category 10 (Low Flow Permits) permit charge paid annually
- Permit charges for Construction Dewatering Permits paid when application is filed

#### Notable Change to 360 CMR 10.023:

 Allows for MassDEP permitted Reclaimed Water Systems that are also permitted by the Authority and Municipality to discharge sludge resulting from the treatment of Municipal Waste into the Sewer





### **Massachusetts Water Resources Authority**

# Chelsea Creek Headworks Upgrade Contract 7161 - Change Order 26

February 20, 2019




# Chelsea Creek Headworks: Screenings Ejection System







### **Chelsea Creek Headworks: Pneumatic Ejection Piping**














# **Chelsea Creek Headworks: Channel 1 Influent Sluice Gate**










### **Massachusetts Water Resources Authority**

# Alewife Brook Pump Station Rehabilitation Contract 7034, Amendment 6

February 20, 2018







# **New Electrical Equipment and Pump Motors**











# **New Standby Generator**






# **Replacement Segment of Alewife Brook Conduit**





### **Bypass Pumping to be Removed**





### **Proposed Amendment 6**

#### **Additional Time**

• Extension of 93 days to align with construction contract

### Out of Scope Services

•	Resident Engineering and Project Administration	\$35,940.18
•	Review of Additional Contractor Submittals	\$32,168.31
•	Change Pump Strategy and PLC Programming	\$26,087.25
		\$94,195.74





### **Massachusetts Water Resources Authority**

# Dam Safety Compliance and Consulting Services Design Repairs and ESDC Contract 7614

February 20, 2019



### **MWRA Dam Maintenance Program**


- Excellent compliance record
- >\$22 million invested
- Regular inspections
  - Correct deficiencies
  - Improve operations
  - Enhance safety and longevity



### **Sudbury Dam Spillway**


- Downstream face masonry repointing and repairs
- Diver inspection of upstream face
- Sudbury Gatehouse vent pipe repair












Extent of mortar deterioration

Clogged weep hole



### **North Dike Reconnection at Leominster Pump Station**

- Potential for wave overtopping during design flood
- Design repair contract to restore dike







### **Foss Dam Overtopping Protection**


- Analysis shows minimal freeboard during design flood (0.3')
- Require overtopping protection due to wave run-up
- Designing of armoring repairs for steep section of dam to withstand overtopping







### **Foss Dam Overtopping Protection on earthen dam**









### **Piezometers at Wachusett North and South Dikes**


• Piezometers required to assess seepage and evaluate stability of the dam



Wachusett Reservoir North Dike from above



North Dike looking west








### **Massachusetts Water Resources Authority**

# Chestnut Hill Emergency Pump Station Improvements Design and Engineering Services During Construction

February 20, 2019




# **Chestnut Hill Emergency Pump Station - Location**





### **Chestnut Hill Emergency Pump Station - Operation**





### **Chestnut Hill Emergency Pump Station - Improvements**

- Interim improvements until tunnel redundancy is complete.
- Mitigate discharge and surge pressure in the event the Dorchester Tunnel needs to be taken out of service (replacement of surge control valves)
- Design of docking station for portable generator

Design of isolation valves between station and tunnel



# **Chestnut Hill Emergency Pump Station - Improvements**





### **Chestnut Hill Emergency Pump Station – Procurement Process**

Proposals Opened on December 20, 2018:

<u>Proposers</u>	<u>Amount</u>
Hazen and Sawyer, P.C.	\$2,074,166.81
Engineer's Estimate	\$2,960,680.00
Stantec Consulting Services Inc.	\$2,997,016.55

- Notice To Proceed: February 2019
- Contract Duration: 66 months

